
- ALL PIPING SHALL BE INSTALLED IN ACCORDANCE WITH NFPA 99, 2018 EDITION. PIPING LAYOUT IS DIAGRAMMATIC ONLY. FINAL ARRANGEMENT WILL BE SITE SPECIFIC. CONTRACTOR WILL BE RESPONSIBLE FOR FIELD VERIFICATION AND COORDINATING ACTUAL LOCATION WITH ALL OTHER TRADES.
- 3. CONTRACTOR SHALL VERIFY MOTOR VOLTAGE, PHASE AND AMP RATINGS BEFORE STARTING ELECTRICAL INSTALLATION; AND MAKE CERTAIN THE VOLTAGE SUPPLIED BY THE HOSPITAL IS THE SAME.
- 4. THE ROOM REQUIRES DEDICATED MECHANICAL VENTILATION WITH AN ALLOWABLE TEMPERATURE VARIANCE OF 40° TO 105°F. (FOR HIGHER AMBIENTS, CONSULT FACTORY)
- 5. ELECTRICAL POWER SHALL BE SUPPLIED FROM THE EQUIPMENT SYSTEM BRANCH OF THE ESSENTIAL ELECTRICAL SYSTEM (EMERGENCY POWER).
- 6. EQUIPMENT, INSTALLATION, AND TESTING OF THE MEDICAL VACUUM SYSTEM SHALL COMPLY WITH NFPA 99, 2018 EDITION, AND ALL STATE AND LOCAL CODES OR ORDINANCES.
- c 7. WIRE LAG & HIGH TEMP. ALARM REMOTE CONTACTS IN THIS CONTROL SYSTEM TO MASTER ALARM SYSTEM AS REQUIRED BY NFPA 99.
- 8. ALL ACCESSORIES, PIPE AND FITTINGS, EXCEPT DISCHARGE SILENCERS, BEYOND INLET AND DISCHARGE PORTS ARE SUPPLIED AND INSTALLED BY OTHERS.
- 9. WHEN DETERMINING THE TOTAL PIPE LENGTH, AND ALL THE STRAIGHT LENGTHS OF PIPE TOGETHER IN ADDITION TO THE NUMBER OF ELBOWS TIMES THE EFFECTIVE PIPE LENGTH FOR THAT PIPE SIZE. (SEE EQUIVALENT PIPE LENGTH TABLE & EXAMPLE CALCULATION IN THE O&M MANUAL)
 - 10. ALWAYS CONSIDER SURROUNDING OCCUPANCIES FOR ALL ROTATING EQUIPMENT. ADDITIONAL **ISOLATION/VIBRATION TRANSLATION REQUIREMENTS** DUE TO SYSTEM LOCATION SHOULD BE DETERMINED AND PROVIDED BY OTHERS.

EXHAUST PIPE SIZE TABLE						
(SEE NOTE 9)						
UNIT SIZE	PIPE LENGTH					
	0-100'	101'-450'	451'-500'			
DX 2 HP	1.50"	2.00"	2.50"			
	0-75'	76'-250'	251'-500'			
DX 3 HP	1.50"	2.00"	2.50"			
	0-100'	101'-400'	401'-500'			
DX 4 HP	2.00"	2.50"	3.00"			
	0-75'	76'-250'	251'-500'			
DX 5.4 HP	2.00"	2.50"	3.00"			



EFFECTIVE PIPE LENGTHS FOR ELBOWS						
PIPE SIZE (IN)	1.50" NPT	2.00" NPT	2.50" NPT	3.00" NPT		
EFF. PIPE LENGTH (FT)	4.0	4.9	6.4	7.9		