


- NOTES:
- 1. DISCHARGE MUFFLER WILL BE SHIPPED LOOSE.
  - 2. DX MODULE WEIGHT: 2,301 LBS.  
SX MODULE WEIGHT: 1,222 LBS.  
(FUTURE EXPANSION MODULE)
  - 200G TANK WEIGHT: 658 LBS    REMOVE INTAKE MANIFOLD BEFORE LIFTING (3 PLACES)
  - CONTROL CABINET WEIGHT: 215 LBS.
  - 3. ☒ INDICATES LIFTING POINT.
  - 4. ● DENOTES CENTER OF GRAVITY.

SYSTEM CONNECTIONS	
ID	DESCRIPTION
I	INLET LOCATION
D	DISCHARGE LOCATION
C	CONDENSATE DRAIN LOCATION
T	TANK DRAIN LOCATION

Revised: a00551998	Date: 4/3/2023	Drawn: JWO	Date: 1/20/2014
 <b>BEACONMEDAES</b>	This drawing and the information contained therein remain the property of BeaconMedaes and may not be used for other than the purpose for which it is loaned without the expressed written permission from BeaconMedaes Engineering.		Scale: <b>D</b>
Description: GENERAL ASSEMBLY 15HP QX-EXP-PX CLAW VAC MOD 200G RECEIVER STANDARD		Part Number: 4107 8549 46	Rev: 03
Sheet 1 of 1		DO NOT SCALE THIS DOCUMENT	