





NOTES:

1. ALL INTERCONNECTING PIPE AND FITTINGS SHALL BE INSTALLED BY THE CONTRACTOR.
2. PIPING LAYOUT IS DIAGRAMMATIC ONLY. FINAL ARRANGEMENT WILL BE SITE SPECIFIC. CONTRACTOR WILL BE RESPONSIBLE FOR FIELD VERIFICATION AND COORDINATING ACTUAL LOCATION WITH ALL OTHER TRADES.
3. CONTRACTOR SHALL VERIFY MOTOR VOLTAGE, PHASE AND AMP RATINGS BEFORE STARTING ELECTRICAL INSTALLATION; AND MAKE CERTAIN THE VOLTAGE SUPPLIED BY THE FACILITY IS THE SAME.
4. THE ROOM REQUIRES DEDICATED MECHANICAL VENTILATION WITH AN ALLOWABLE TEMPERATURE VARIANCE OF 40° TO 105°F. (FOR HIGHER AMBIENTS, CONSULT FACTORY)
5. ALL ACCESSORIES, PIPE AND FITTINGS, EXCEPT DISCHARGE SILENCERS, BEYOND INLET AND DISCHARGE PORTS ARE SUPPLIED AND INSTALLED BY OTHERS.
6. ALLOW 36 INCHES IN FRONT OF CONTROL PANEL FOR MAINTENANCE AND VENTILATION, ALL OTHER SIDES REQUIRE 24 INCHES OF CLEARANCE.
7. WHEN DETERMINING THE TOTAL PIPE LENGTH, AND ALL THE STRAIGHT LENGTHS OF PIPE TOGETHER IN ADDITION TO THE NUMBER OF ELBOWS TIMES THE EFFECTIVE PIPE LENGTH FOR THAT PIPE SIZE. (SEE EQUIVALENT PIPE LENGTH TABLE & EXAMPLE CALCULATION IN THE O&M MANUAL)



EFFECTIVE PIPE LENGTH FOR ELBOWS		
PIPE SIZE (IN)	2.00" NPT	3.00" NPT
EFF. PIPE LENGTH (FT)	4.9	7.9

EXHAUST PIPE SIZE TABLE		
UNIT SIZE	PIPE LENGTH	
	0-75'	76'-500'
DX 5HP	2.00" NPT	3.00" NPT
	0-400'	401'-500'
DX 7.5HP	3.00" NPT	4.00" NPT

--- FIELD PIPING INLET  
=== FIELD PIPING OUTLET

(200 GALLON RECEIVER SHOWN)

Revised: MDB	Date: 07/10/2019	Drawn: MDB	Date: 11/21/2017
		Scale: 1/10	
Description: INSTALLATION DIAGRAM LAB DX 5-7.5HP LUBE VAC SPC		Part Number: 4107 8563 22	
		DN: BM190347	Rev: 01
Sheet 1 of 1		DO NOT SCALE THIS DOCUMENT	